





## DP0074 One Direction T-2A Load Holding Valve Body Subassembly, #6 O-Ring End Ported

## Counterbalance Valve Symbol











Pilot Operated Check Valve Symbol





This manifold is made from cold drawn C1018 flat bar and is designed to be welded to Schedule 80 seamless pipe or DOM tubing. For best welding results, fit tubes, tack into location, preheat to 150°-200°F and weld with E80SD2 wire. Welding can be done with E70 filler material if E80 is not available.